PROFORMA OF SCHEDULES
SCHEDULE – A
SCHEDULE OF QUANTITIES

Name of work: **Construction of Synthetic Tennis Court (Asphalt base - 8 Layer) at Indira Nagar (IAS Officers Quarters), Gorimedu, Puducherry (Second Call).**

NIT No. : **84/PW/SBDII/2025-2026.**

Name of Division : **Executive Engineer, Special Buildings Division-II, PWD, Puducherry.**

Sl. No.	Code No.	Specification	Quantity	Unit	Rate	Amount
1	2.8.1	Earthwork in excavation by mechanical means (Hydraulic excavator) / manual means in foundation trenches or drains (not exceeding 1.5m in width or 10 sqm on plan), including dressing of sides and ramming of bottoms, for all lift, including getting out the excavated soil and disposal of surplus excavated soil as per direction of Engineer-in-charge , within a lead of 50m - all kinds of soil	59.00	cum	272.13	16056
2	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20cm in depth, consolidating each deposited layer by ramming and watering, lead upto 50m and all lift	22.00	cum	165.29	3636
3	2.31	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth upto 30cm measured at a height of 1m above ground level and removal of rubbish upto a distance of 50 m outside the periphery of the area cleared.	2750.00	sqm	16.20	44550
4	2.33.1	Felling trees of the girth (measured at a height of 1m above ground level) including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material - beyond 30cm girth upto and including 60cm girth.	6.00	each	488.59	2932

5	2.33.2	Felling trees of the girth (measured at a height of 1m above ground level) including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material - beyond 60cm girth upto and including120cm girth.	6.00	each	2189.75	13139
6	4.1.3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:2:4 (1 cement : 2 fine aggregate : 4 graded stone aggregate 20mm nominal size)	11.50	cum	7402.94	85134
7	4.1.10	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - all work upto plinth level - 1:5:10 (1 cement : 5 fine aggregate : 10 graded stone aggregate 40mm nominal size)	12.50	cum	6075.30	75941
8	4.2.3	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc. upto floor five level, excluding the cost of centering ,shuttering and finishing - 1:2:4 (1 cement : 2 fine aggregate : 4 graded stone aggregate 20mm nominal size)	25.50	cum	8766.81	223554
9	4.3.1	Centring and shuttering including strutting , propping etc. and removal of form work for - foundations, footings, bases for columns	24.00	sqm	409.56	9829
10	4.3.2	Centring and shuttering including strutting , propping etc. and removal of form work for - retaining walls, return walls, walls (any thickness) including attached pilasters, buttresses, plinth and string courses fillets, kerbs and steps etc	330.00	sqm	847.05	279527
11	9.165.1B	Providing and fixing of 65 mm Navatal lock of 7 levers with 3 keys etc complete	2.00	each	692.10	1384

12	10.16.1	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting , hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete - hot finished welded type tubes	2200.00	kg	183.14	402908
13	10.25.2	Steel work welded in built up sections / framed work , including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required - in gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	450.00	kg	167.67	75452
14	10.28	Providing and fixing stainless steel (grade 304) railing made of hollow tubes, channels, plates etc., including welding ,grinding. Buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete. i/c fixing the railing with necessary accessories & stainless steel dash fasteners, stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts,fasteners etc.,)	560.00	kg	689.02	385851
15	13.1.1	12mm cement plaster of mix -1:4 (1 cement : 4 fine aggregate)	125.00	sqm	332.60	41575
16	13.9.1	Cement plaster 1:3 (1 cement : 3 fine aggregate) finished with a floating coat of neat cement - 12mm cement plaster.	112.00	sqm	420.52	47098
17	13.48.1	Finishing with deluxe multi surface paint system for interiors and exteriors using primer as per manufacture's specification - Two or more coats applied on walls @ 1.25 ltr / 10 sqm over and including one coat of special primer applied @ 0.75 ltr / 10 sqm.	125.00	sqm	168.62	21078
18	13.61.1	Painting with synthetic enamel paint of approved brand and manufacture to give an even shade - Two or more coats on new work	100.00	sqm	151.31	15131

19	16.70.2	Providing and fixing G.I.chain link fabric fencing of required width in mesh size 50 x 50 mm including strengthening with 2mm dia wire or nuts , bolts and washers as required complete as per direction of Engineer-in-charge - Made of G.I.wire of dia 4mm , PVC coated to achieve outer dia not less than 5mm in required colour and shade	400.00	sqm	828.03	331212
20	4.12A.1	Providing , laying , spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the material with water at OMC in mechanical mix plant carriage of mixed material by tipper to site , laying in uniform layer by manual means in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density - Using vibratory roller	135.00	cum	2106.08	284321
21	5.1 MO	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg/sqm using mechanical means. (As per MoRTH specification, 4th Revision)	680.00	sqm	40.22	27350
22	5.2 MO	Providing and applying tack coat with bitumen emulsion using emulsion pressure distributor at the rate of 0.20 kg. per sqm. on the prepared bituminous / granular surface cleaned with mechanical broom. (As per MoRTH specification, 4th Revision)	680.00	sqm	14.15	9622
23	5.3B MO	Providing and laying bituminous macadam with hot mix plant of capacity not less than 40 -60 TPH using crushed aggregates of specified grading premixed with bituminous binder, transported to site, laid over a previously prepared surface with paver finisher to the required grade, level and alignment and rolled as per clauses 501.6 and 507.7 of MoRTH specification, 4th Revision, to achieve the desired compaction. – using grade II metal and bitumen - VG30	52.00	cum	7617.41	396105

24	5.8B.1 MO	Providing and laying bituminous concrete with HMP of capacity not less than 40 to 60 TPH using crushed aggregates of specified grading, premixed with bituminous binder @ 5.4 to 5.6 percent of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per clause 509 of MoRTH specification, 4th Revision, complete in all respects - Using grade-II material.- Bitumen -VG30	21.00	cum	10051.88	211089
25	NON PSR	Providing and laying Acrylic Synthetic 8- layer system (ITF Approved Product) consist of Primer (1-Layer), Resurfacer (2nd & 3rd Layer), Cusion (4th, 5th & 6th Layer), Colour coat (7th & 8th Layer) including Line marking. The thickness of eight layer should be 3.00mm to 3.50mm. The rate including transportation to site and all taxes.	680.00	sqm	1227.00	834360
26	NON PSR	Providing and fixing International Tennis Federation Standard Type Tennis poles of special internal ratchet system for tightening the rope / net (1-Set) and providing and fixing of ITF standard Tennis Net (1-No). The rate including transportation to site and all taxes.	1.00	set	45000.00	45000
					Estimated Cost	**3883834**

Certified that the NIT contains 1 to 114 Pages.

Certified that the NIT contains 26 items in the above Schedule of Quantities.

This Nit approved for an amount of Rs.38,83,834/- (Inclusive of GST @ 18%) (Rupees thirty eight lakh eighty three thousand eight hundred and thirty four only).

-//APPROVED//-